

<b>PHILIPPINE SCIENCE HIGH SCHOOL SYSTEM</b>		<b>REQUEST FOR QUOTATION FORM &amp; NOTICE</b>	
		<b>GOODS</b>	
<b>Office/Campus:</b>	PHILIPPINE SCIENCE HIGH SCHOOL-ZAMBOANGA REGION CAMPUS		
<b>Address/Contact Details:</b>	Cogon, Dipolog City		

GENTLEMEN: Quotation No.: **2021-03-065**  
Date: **March 15, 2021**

May we request for quotation on materials enumerated hereunder. If you are interested and in a position to furnish the same, we shall be glad to have your best prices.

Delivery within \_\_\_\_\_ working days upon receipt of approved Purchase Order (PO).


In case of failure to make the full delivery/completion within the time specified as offered/required, the Supplier/ Contractor shall be liable for liquidated damages/penalty of one-tenth (1/10) of one percent (1%) of the Contract Price per calendar day of delay minus the value of the delivered/completed portion(s) of the approved P.O./Contract.

Item #	Qty	UNIT	ITEM/DESCRIPTION	UNIT COST	TOTAL COST
<b>PRICES MUST BE Tax (VAT) INCLUSIVE</b>					
<b>Supply and Delivery of Materials and Installation of 10 Airconditioning Units</b>					
	1	lot	Supply and Delivery of Materials and Installation of 10 Airconditioning Units		
Specifications:					
-install 3 units 1.0HP; 1 unit 1.5HP; 1 unit 2.0HP; and 5 units 2.5HP					
-copper tube should be soft-drawn, 5/8" x 0.028					
-materials needed other than the copper tube shall also be provided by the service provider/installer					
-service provider/installer to make layout plan and specifications as to shapes and depths of holes to be made where connections/copper wires are to pass through, with reference to the attached HVAC Layout Plan of the Academic Bldg 2 of the campus and drawing of initial plan where connections to pass through					
-labor charge for making of holes for the copper wires and other materials to pass through or installed shall NOT be included in this procurement					
-total gross estimated copper tube requirements is 460 feet; site inspection is necessary					
-with warranty of at least one (1) year from installation date					
-service provider/installer should present PhilGEPS-registered, business permit and DTI/SEC registration					
Location: Ground Floor of Academic Bldg 2 of PSHS-ZRC at Brgy. Cogon, Dipolog City					
<b>TOTAL</b>					

**Approved Budget: 200,000.00**

Delivery Term within 15 working days from receipt of PO  
 Delivery Time 8:00:00 AM - 4:00 PM  
 Payment Term within 30 days

Very truly yours,

  
**HAZEL R. LAGAPA**  
 BAC Chairperson

**PRICES IN THE ABOVE OFFER ARE CERTIFIED TRUE AND CORRECT:**

Authorized Company Representative :

\_\_\_\_\_  
 (Signature Over Printed Name)

Company Name :  
 Address :

Telephone nos. :  
 T.I.N. :

**IMPORTANT**

- Prices must be written clearly.
- If offering a substitute/equivalent, specify the brand and make.