

		<p>cable trays and with complete support as ceiling works will be done in the next phase. A fitting shall be provided on the end(s) of the conduit to protect the cables from abrasion.</p> <p>To:</p> <p>ii. Installation and laying out of cables, wires, race-ways/cable trays and conduits at Basement, 1<sup>st</sup> &amp; 2<sup>nd</sup> Floor.</p>
<b>6. ICT installation at 3<sup>rd</sup> Floor</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 2.j.iv Construction; ICT</p>	<p><b>Deletion</b></p> <p><del>iv. Cable installation at 3<sup>rd</sup> Floor shall be laid thru cable trays with complete support. A fitting shall be provided on the end(s) of the conduit to protect the cable from abrasion.</del></p>
<b>7. 4" CHB Filing</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 3.III. Bill of Quantities; Structural Works</p>	<p><b>Clarification on work coverage</b></p> <p>From: Complete interior walls with plastering</p> <p>To: Complete interior walls with plastering at <b>Basement, 1<sup>st</sup> and 2<sup>nd</sup> Floor only.</b></p>
<b>8. Exterior Wall Painting</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 3.IV. Bill of Quantities; Architectural Works</p>	<p><b>Deletion</b></p> <p>From: <del>Complete exterior walls</del>; Complete interior walls at Basement, First and Second Floor</p> <p>To: Complete interior walls at Basement, First and Second Floor</p>
<b>9. Cables, Wires, Race-ways &amp; Conduits</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 3.VII. Bill of Quantities; Electrical Works</p>	<p><b>Clarification</b></p> <p>Installation works shall not cover at Third Floor</p>
<b>10. CCTV, CATV</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 3.VIII. Bill of Quantities; ICT</p>	<p><b>Deletion</b></p> <p>From: Laying out of pipe conduits, cables and outlets. Installation works at Basement, First, Second <del>and Third Floor</del>. Cables shall be CAT 6 UTP cable.</p> <p>To: Laying out of pipe conduits, cables and outlets. Installation works at Basement, First, and Second Floor. Cables shall be CAT 6 UTP cable.</p>
<b>11. Voice, Data and WIFI</b>	<p>SCOPE OF WORK</p> <p>III. Scope of Work</p> <p>Item 3.VIII. Bill of Quantities; ICT</p>	<p><b>Deletion</b></p> <p>From: Laying out of pipe conduits and wires, mounting junction boxes, outlets, pulling wiring, grounding and overhead service wire. Installation works at Basement, First, Second <del>and Third Floor</del>.</p>